

Unit 10013

Solar Saturn 10 Mark ii Gen Set

Mobile Modular Unit in 40' ISO Container

1201 engine rebuilt at alcor and tested at GTA

800kw 480v, 60hz

GE PowerBreakii 1600 amp switchgear

24vdc control system with charger and 4x6v battery bank

5kva 120v auxiliary power

Woodward Atlas ii Controller

HMI Interface

IR pneumatic starter

AGV10 fuel control

Triton gas coalescing filter vessel

note: Marki oil cooler