

G.L.M. TANKS & EQUIPMENT LTD.

NISKU, ALBERTA

BATTLEFORD, SASK.


API *** ED. 1 9 APP. SERIAL No. J-99-088-1 YEAR BUILT 1999

| | | | | |
|--|--------------|------------|-------------|-----|
| NOM DIA | 17.25 FT. | NOM CAP | 2000 | BBL |
| NOM HT | 48.0 FT. | SHELL THK | 3/16 / 1/4 | IN. |
| BTM THK | 1/4 IN. | SHELL MATL | A-36 OR EQ. | |
| DECK THK | 1/4 IN. | BTM TYPE | FLAT | |
| S.G. | 1.0 | D.P. | ATMOSPHERIC | |
| D.M.T. | 11 F | S.R. | N/A | |
| D.L.L. | 48.0 FT. | EQUIP NO | N/A | |
| SERVICE | PROCESS TANK | | | |
| *** IN ACCORDANCE WITH API650 (MODIFIED) | | | | |

0'-7 1/2"

0'-5 3/8"

PIECE NP-A G.L.M. NAMEPLATE DETAIL




PIECE NP-C NAMEPLATE BRACKET BEFORE FORMING

[illegible]


NOTES:

1. ALL TEXT THAT IS TO BE STAMPED ON THIS NAMEPLATE SHALL BE STAMPED IN 1/4" HIGH LETTERING.
2. NAMEPLATE IS TO BE INSTALLED ONLY AFTER TANK HAS BEEN SAND BLASTED AND PAINTED. (IF REQ'D)



PIECE NP-C NAMEPLATE BRACKET

AFTER FORMING

| | | | |
|---|---|--------------------|----------|
|  G.L.M. Tanks & Equipment Ltd. AN ITEQ STORAGE SYSTEMS COMPANY | | | |
| ENGINEERING: NISKU | | FABRICATION: NISKU | |
| PROJECT ENG. APPROVAL & DATE: | 1► 06/10/99 | REV'D AS SHOWN | JD |
| CHECKED BY & DATE: | | | |
| DRAWN BY J. OVELSDON & DATE: JUNE 1, 1999 | | | |
| TOLERANCES: | NO | DATE | REVISION |
| API 650 9th EDITION | DESCRIPTION: NAME/PLATE DETAIL CANADIAN CRUDE SEPARATORS 17'-3" O.D. x 48'-0" HIGH PROCESS TANK DRAYTON VALLEY, AB | | |
| CRN # / NATL BD # N/A | SCALE: N.T.S. | | REV. |
| PURCHASE ORDER # 811 | DRAWING J-99-088-1-NP NUMBER | | 1 |